

Using BrR To Evaluate Bascule Bridges

2018 RADBUG MEETING – BOISE, IDAHO
AUGUST 7-8, 2018



Presenters:

Carolyn Kois, PE (*Collins Engineers, Inc.*)

ckois@collinsengr.com

Jim Surber, PE, SE (*Alfred Benesch & Co.*)

jsurber@benesch.com



A Joint Venture Teaming of Alfred Benesch & Company and Collins Engineers, Inc.




Using BrR To Evaluate Bascule Bridges

Summary of Presentation

- Background on CDOT & CBIT
- LaSalle St. and Lake St. Bascule Bridges – Carolyn Kois, P.E.
- Roosevelt Rd. and Cermak Rd. Bascule Bridges – Jim Surber, P.E, S.E.




Five Bridge Types Maintained by



2018 RADBUG MEETING - BOISE, IDAHO




Chicago Bascule Bridges



2018 RADBUG MEETING - BOISE, IDAHO



Chicago Bascule Bridges



2018 RADBUG MEETING - BOISE, IDAHO



Who is CBIT?

Chicago
Bridge
Inpection
Team



A Joint Venture Teaming of Alfred Benesch
& Company and Collins Engineers, Inc.


2018 RADBUG MEETING - BOISE, IDAHO






A Joint Venture Teaming of Alfred Benesch & Company and Collins Engineers, Inc.

- Bridge Inspections
 - Routine, Special, Fracture Critical, Underwater and Element Level
 - Mechanical and Electrical of movable bridges
 - NDT including UT testing
 - Confined spaces
 - Rope access, barges and man-lifts
- On-Call Engineering Services
 - Bridge repairs
 - Emergency services
 - Bascule bridge balancing
- Load Rating



LaSalle St. Bascule

Single Level Double Leaf Trunnion Type Bascule




2018 RADBUG MEETING - BOISE, IDAHO



LaSalle St. Bascule

Bascule Components and Supports



LaSalle St. Bascule

Original Construction


Construction/Repair History

- 1928 Original Construction
- 1969 Timber Deck Replaced with Steel/Concrete Deck rebalancing of counterweight




Historical Photo of La Salle Street Bridge
Source: Armour Engineer, Volume 22, No. 3, 1931

Design Load



CONDITION OF MAXIMUM LIVE LOADING OF TRUSSES.
Loads shown are per lineal foot.



Geometry

- 219'-10" between live load bearings
- 11'-6" live load bearings to trunnions
- 35"-3" trunnions to anchor columns


LaSalle St. Bascule Carrying Elements

- Fixed span elements mostly rated in BrR
- Supplemental analysis required outside of BrR for some carrying elements



The concrete substructure of the bridge rests on massive concrete piers that are built down to bed rock.

Construction of Bridge
Source: Armour Engineer, Volume 22, No. 3, 1931



Section Through Counterweight Pit Showing Structural Detail


LaSalle St. Bascule

Dead Load Forces

Dead Loads

- Truss member self weight
- Floorbeams
- Stringers
- Cantilever sidewalks
- Lateral Bracing
- Deck
- Counterweight

Steel Grating Deck with Concrete Infill at Centerlock and Floorbreaks




- Non-composite deck
- Deck thickness/weight adjusted to reflect weight of open steel grating
- Additional weight of concrete fill applied as distributed loads

LaSalle St. Bascule Dead Load Balancing

Balanced Condition


- Counterweight for DL model based on design and rehab plans
- Bascules rebalanced after repairs/alterations/maintenance
- Reaction at live load bearing is calculated for balanced condition (slightly nose-heavy)
- Counterweight is verified by comparing DL reaction at LL bearing reaction based on plan weight to LL bearing reaction calculated for balanced condition




LaSalle St. Bascule

Load Stages


Dead Load: supported by trunnion only (with minimal DL at LL bearing when bridge is closed)



Live Load: supported by trunnion, LL bearing & anchor column (with shear transfer at centerlock)



Pedestrian load included with live load



■ Half deck line locations in BrR set to reflect the loaded panel points for live load

LaSalle St. Bascule

Live Load



Vehicle and Pedestrian Load

Supports

- Pin Support at Trunnion
- Roller Support at LL Bearing
- Roller Support at CW Bumper

Centerlock

- Centerlock transfers shear
- Does not transfer moment or axial load)



LaSalle St. Bascule

Verification of Dead Load Support Conditions

Location	Design Stress Sheet DL (k)	AASHTOWare Member	STAAD DL balance model (no centerlock or heel lock)	Location	Design Stress Sheet DL (k)	AASHTOWare Member	STAAD DL balance model (no centerlock or heel lock)
Top Chord		1-3	0	Diagonals	-71	0-3	-87
	-59	3-5	-72		-171	2-5	-214
	-198	5-7	-247		-225	4-7	-243
	-372	7-9	-434		-278	6-9	-277
	-582	9-11	-643		-266	8-11	-239
	-762	11-13	-803		-153	10-13	-113
	-866	13-15	-883		176	12-15	204
	-1160	15-17	-1128		-730	14-14a	-738
Bottom Chord	59	0-2	71	Rear Members	-801	14a-15	-752
	198	2-4	245			14a-16	0
	371	4-6	431		454	14-16	477
	572	6-8	631		405	14-18	393
	749	8-10	788		412	18-20	399
	848	10-12	865		984	15-16	910
	856	12-14	862		1537	16-17	1506
	5	0-1	2		-1179	17-19	-1176
Verticals	42	2-3	50				
	87	4-5	105				
	132	6-7	141				
	138	8-9	128				
	179	10-11	160				
	73	12-13	39				

Note: Numerous structure components, including the deck, have been modified since original construction. Original dead load forces are provided for information, however the dead load used for analysis was calculated based on the current structure geometry.


Location	Member	Bridge Closed						Bridge Opening or Fully Opened					
		Dead Load	Live Load No Shear Lock	Impact Coefficient	Impact Combined Stress	Col A* 50% Total Stress	Col B* 50% Total Stress	D.L. Closed	D.L. Open	20% Vib	20% Wind	20% Combined Stress	20% Reversed Stress
1-3													
3-5	-59.0 -59.0	-126.0 <small>(6.75+12.55)+300</small>	-100 <small>+100</small>	0.97	-18.0 -260.0 <small>(6.75+33.00)+100</small>	-108 +130 +98.0 <small>+108 +130 +98.0</small>	± 49.0 <small>± 49.0</small>	-309.0 <small>+147.0</small>	-59.0 -2.0 <small>-59.0 -2.0</small>	-12.0 +11.0 <small>-12.0 +11.0</small>	-7.0 +9.0 <small>-7.0 +9.0</small>	± 4.0 <small>± 4.0</small>	-75.0 <small>+13.0</small>
5-7	-198.0 -221.0	-149.0 <small>(6.75+12.55)+300</small>	-100 <small>+100</small>	0.88	-33.0 -60.0 <small>(6.75+72.55)+300</small>	-121 +18.0 +35.0 <small>-121 +18.0 +35.0</small>	± 17.0 <small>± 17.0</small>	-619.0 <small>+52.0</small>	-198.0 -22.0 <small>-198.0 -22.0</small>	-40.0 +39.0 <small>-40.0 +39.0</small>	-238.0 <small>+17.0</small>	± 8.0 <small>± 8.0</small>	-246.0 <small>+25.0</small>

LaSalle St. Bascule Load Rating Analysis

Floorbeams and Stringers

- Moveable portion modeled in BrR in truss superstructure definition
- Fixed spans modeled in BrR as separate superstructure alternative

Note: BrR does not model simple span floorbeams when there are more than 2 truss lines in a bridge. Floorbeams are analyzed as continuous so workaround is required to model them as simple span between trusses.



Lake St. Bascule

Double Level Double Leaf Trunnion Type Bascule



2018 RADBUG MEETING - BOISE, IDAHO



Lake St. Bascule Original Construction


Construction/Repair History

- 1914 Original Construction
- 1994 lower level floor system replacement and rebalancing of counterweight
- Various other repairs over the history of the bridge

Geometry



- 245'-3" between live load bearings
- 14'-0" live load bearings to trunnions
- 37"-7" trunnions to heel locks

Design Load



OLD AND NEW DRAWBRIDGES OVER THE CHICAGO RIVER AT LAKE ST.

Live load for floor system, hangers and posts, a floor load of 100[#] per square foot of sidewalk and roadway combined with two 50 ton electric cars on each track, or with one 24 ton truck on any part of the roadway




Space occupied by above loadings assumed as 10 ft in width

Live load for trusses, 2000[#] per lineal foot of each track, and 100[#] per square foot of sidewalk and roadway surface not occupied by the track loads

HS 20 Design Live Load for Lower Level Floor System constructed in 1994 to replace original lower level framing

Lake St. Bascule Load Stages

Dead Load: supported by trunnion (minimal DL reaction at LL bearing for balanced condition)



Live Load: supported by trunnion, LL bearing & heel lock

2 Stage Load Model: Dead load force overrides are required for AASHTOWare analysis since dead load and live load have different support conditions


Lake St. Bascule

Live Load Supports

Vehicle and Pedestrian Load on Lower Level & CTA Loading on Upper Level


Supports

- Pin Support at Trunnion
- Roller Support at Live Load Bearing (verified no uplift)
- Roller Support at Heel Lock



Centerlock


- Centerlock transfers shear
- Does not transfer moment or axial load)



Lake St. Bascule

Dead Load Analysis

Input of Dead Load Force Overrides




Verification of Dead Load Forces used for Analysis

Member	Truss Element	DL Force (kip)	LL Force				Capacity	
			Comp. (kip)	IF	Tens. (kip)	IF	Comp. (kip)	Tens. (kip)
P10P12	Lower-Chord	-688.00	-153.79	1.28	0.11	1.21	-2629.98	3142.80
P8P10	Lower-Chord	-346.00	-94.84	1.28	0.97	1.21	-1507.39	1805.40
P6P8	Lower-Chord	-345.00	-94.31	1.28	1.02	1.21	-1884.35	2256.60
P4P6	Lower-Chord	-88.00	-34.64	1.28	2.37	1.21	-553.48	660.00
P2P4	Lower-Chord	-88.00	-34.38	1.28	2.44	1.21	-553.48	660.00
P0P2	Lower-Chord		-0.21	1.28	0.06	1.21	-473.06	564.00
P10'P12'	Lower-Chord	-688.00	-153.49	1.28	0.11	1.21	-2629.98	3142.80
P8'P10'	Lower-Chord	-346.00	-94.59	1.28	0.97	1.21	-1507.39	1805.40
P6'P8'	Lower-Chord	-345.00	-94.05	1.28	1.06	1.21	-1507.58	1805.40
P4'P6'	Lower-Chord	-88.00	-34.53	1.28	2.40	1.21	-553.48	660.00
P2'P4'	Lower-Chord	-88.00	-34.28	1.28	2.47	1.21	-553.48	660.00
P0'P2'	Lower-Chord		-0.21	1.28	0.06	1.21	-473.06	564.00
P12P18	Lower-Chord	-413.00	-49.96	1.30	3.48	1.30	-2439.74	2502.90
P12'P18'	Lower-Chord	-413.00	-49.87	1.30	3.48	1.30	-2439.74	2502.90
P16P18	Lower-Chord	-459.00	-47.11	1.30	3.77	1.30	-2000.00	2000.00
P16'P18'	Lower-Chord	-459.00	-47.02	1.30	3.77	1.30	-2000.00	2000.00
P11P13	Upper-Chord	517.00	-0.31	1.21	128.82	1.28	-2770.65	2695.80
P9P11	Upper-Chord	517.00	-0.41	1.21	128.55	1.28	-2770.65	2695.80
P7P9	Upper-Chord	194.00	-2.27	1.21	61.46	1.28	-1204.46	1162.20
P5P7	Upper-Chord	194.00	-2.30	1.21	61.18	1.28	-1204.46	1162.20
P3P5	Upper-Chord	23.00	-2.06	1.21	14.55	1.28	-1030.56	995.40
P1P3	Upper-Chord	23.00	-2.12	1.21	14.25	1.28	-927.32	895.80

Lake St. Bascule

Combined Upper and Lower Level Live Load

- Upper Level – CTA Trains
- Lower Level – Vehicles
- Upper and lower loads analyzed on separate superstructure alternatives in BrR
- Truss loads combined to calculate rating factors for concurrent upper and lower level live loading



Combined Opr. RF (Comp.)	Combined Opr. RF (Tension)
1.31	99.00
1.50	30.88

LL Force (CTA)				LLDF (CTA)
Comp. (kip)	IF	Tens. (kip)	IF	
-190.89	1.28	4.62	1.21	1
-50.51	1.28	7.48	1.21	1

Member	Truss Element	DL Force (kip)	LL Force				Capacity	
			Comp. (kip)	IF	Tens. (kip)	IF	Comp. (kip)	Tens. (kip)
P6P8	Lower-Chord	-345	-139.71	1.28	2.03	1.21	-1507.58	1805.4
P4P6	Lower-Chord	-88	-59.48	1.28	4.03	1.21	-553.48	660

Roosevelt Rd. Bascule

Deck Truss Double Leaf Trunnion Type Bascule



2018 RADBUG MEETING - BOISE, IDAHO



Roosevelt Rd. Bascule Original Construction


Construction/Repair History

- 1928: Original Construction
- 1973-1975: Isolated repairs of bascule truss, deck replacement and rebalancing
- 1994: Major rehabilitation including replacement of floorbeams, stringers and lateral bracing in movable span and rebalancing
- 1,164 existing plan sheets


Geometry

- 204'-0" CL to CL Trunnions
- 28'-9" End Span (each side)



• Design Load



Roosevelt Rd. Bascule Bascule Structure Components and Supports





Roosevelt Rd. Bascule Plan and Elevation



2018 RADBUG MEETING - BOISE, IDAHO




Roosevelt Rd. Bascule Cross Section



Roosevelt Rd. Bascule Load Stages


BRIDGE OPEN

Dead Load + Wind Load



BRIDGE CLOSED

Dead Load + Live Load (Including Pedestrian Load)



Roosevelt Rd. Bascule Dead Load Forces


Dead Loads

- Truss member self weight
 - Floorbeams
 - Stringers
 - Cantilever sidewalks
 - Lateral Bracing
 - Deck (Steel Grating)
 - Counterweight
 - Inspection Walkway

* Ctrwt. Pockets to provide adjustment from 2% below to 4% above moment required to balance leaf.

Roosevelt Rd. Bascule Dead Load Balancing

- **1928: Original Balancing**
 - **1973: Rebalancing**
 - **1994: Rebalancing**



C.G. AND MOMENT - FIGURES ARE PER LEAF
BALANCING CALCULATIONS

ITEM	NO.	UNIT WEIGHT	IN. PER UN. FT.	LENGTH WEIGHT	TOTAL WEIGHT PER LEAF (LBS)	"X" FEET	"Y" INCHES (FT.-IN.)	"Z" INCHES	"W" MOMENT (IN.-LBS)
MATERIALS REMOVED									
1	FB 9-9		1		24,480.00	101.13	2,475	540.00	64,60
2	FB 4-2		1		22,440.00	86.35	2,537	783.75	60,00
3	FB 4-2		1		22,730.00	21.58	1,627	0.156	2,700
4	FB 8-5		1		21,275.00	58.81	1,208	875.30	56,70
5	FB 8-5		1		18,780.00	42.04	795	546.75	41,90
6	FB 10-10		1		24,670.00	27.27	672	775.57	44,60
7	FB 10-12		1		38,730.00	14.88	576	108.75	41,00
8	BOTTOM STRUT		1		6,154.00	12.50	79	920.00	-142.00
LATERAL BRACING:									
9	G-0 TO 2-2		1		3,930.00	93.74	365	388.20	14,00
10	2-2 TO 4-4		1		3,795.00	78.97	295	524.84	9,50
11	4-4 TO 6-6		1		3,795.00	64.20	241	505.74	6,00
12	6-6 TO 8-8		1		4,040.00	49.43	241	505.74	22,530
13	8-8 TO 10-10		1		4,040.00	35.99	275	526.66	57,00
14	10-10 TO 12-12		1		5,940.00	19.89	118	116.90	-107.00
15	WT 15X 49.5 ON FB's	5			14,040.00	58.87	798	454.80	115.80
ROADWAY STRINGERS:									
16	FB 10-10 TO 10-10 (16X45)	18			184,370.00*	84.20	8,700	554.00	119.90
17	FB 10-10 TO REAR BREAK (W/4X 61")	19			34,040.00*	18.44	627	697.60	121.30
18	RDMY. STRINGER SUPPORTS (# REAR BREAK)	6			6,740.00*	18.85	133	991.2*	110.60
19	ORIGINAL STRINGERS, TOP 10 TO 10 REAR BREAK				28,500.00	19.77	523	905.00	98.00
20	ORIGINAL STRINGERS STUBS # FLOORBEAMS				8,500.00	64.20	417	300.00	27.52
21	5" CONC. FILLED ROADWAY DECK	58.0 PSF			141,580.00*	62.37*	8,310	344.60	130.30
22	5" OPEN ROADWAY DECK WELDMENT	19.1 PSF			86,870.00*	52.07	4,523	320.95	130.60
23	REAR BREAK				11,130.00*	9.97	110	927.60	129.49
24	CENTER BREAK				9,040.00	101.32	915	832.80	122.50
25	CENTER BREAK WELDMENT SUPPORT	1			3,210.00	101.17	324	755.70	116.30
26	ROADWAY MEDIAN				30,360.00	55.82	1,694	695.20	135.00
27	FENCE LING. (SUPPORTS)				7,400.00	32.99	432	415.20	143.00
28	STEEL CURB (LING. GROUT)				42.30	184.00	56.10	456.00	145.80
TOTALS (EAST LEAF)									
					699,209.00*		37,364	748.63*	67,618,793.50
TOTALS (WEST LEAF)									
					698,209.00*		37,364	748.63*	67,618,793.50

C.G. AND MOMENT - FIGURES ARE PER LEAF
BALANCING CALCULATIONS

ITEM	NO.	UNIT	WEIGHT PER UNIT	LENGTH	WEIGHT	TOTAL WEIGHT PER LOAD (LBS.)	"E" FEET	"E" MOMENT (FT-LBS.)	"E" INCHES	"E" MOMENT (IN-LBS.)
MATERIALS ADDED										
1	F B 0-0	1				15,500.00	101.25	1,569,370.00	78.32	1,182,960.00
2	F B 2-2	1				15,760.00	101.35	1,565,533.40	78.32	1,185,952.40
3	F B 4-4	1				16,230.00	96.81	922,056.30	65.74	745,960.00
4	F B 6-6	1				16,230.00	96.81	922,056.30	65.74	745,960.00
5	F B 8-8	1				16,230.00	96.81	922,056.30	65.74	745,960.00
6	F B 10-10	1				16,790.00	77.27	539,767.50	35.97	311,840.00
7	F B 12-12	1				20,860.00	15.95	125,150.00	-142.00	1,247,700.00
8	LATERAL STRU. LATERAL BRACING:	1								
9	0-0 TO 2-2	1				5,618.00	93.74	506,611.32	13.25	74,438.00
10	2-2 TO 4-4	1				5,618.00	78.57	443,703.84	8.75	49,163.75
11	4-4 TO 6-6	1				5,621.00	60.42	360,706.72	5.25	29,513.40
12	6-6 TO 8-8	1				5,621.00	48.82	288,709.70	3.25	20,353.12
13	8-8 TO 10-10	1				5,624.00	34.66	197,827.63	-33.25	300,533.12
14	10-10 TO 12-12	1				5,702.56	19.59	113,424.93	-107.25	164,450.84
15	ROADWAY RAILINGS									
16	#B 0-0 TO 8-8	24				21,763.00	78.52	1,820,307.10	151.45	2,125,560.82
17	#B 8-8 TO 10-10	24				21,763.00	60.01	1,398,632.66	133.31*	1,641,154.22
18	5" CONC. FILLED ROADWAY DECK	49.3 (PSF)				331,468.00	56.01	18,985,832.66	133.31*	64,401,154.22
19	ROADWAY DECK CANTILEVER END SPANNING 10' 0" (120'L)					55,695,504.00	53.75	206,812.75	131.31*	7,833,784.00
20	THRU ROADWAY (EAST)					11,041.00	101.45	1,120,219.85	133.67	1,475,850.47
21	THRU SIDEWALK (EAST)					11,041.00	101.45	1,120,219.85	133.67	1,475,850.47
22	THRU SIDEWALK (WEST)					183,600.00	101.45	16,589.71	143.00	23,380.80
23	THRU SIDEWALK (WEST)					497.15	14.15	583.44	143.00	65,372.45
24	ROADWAY SPAN					1,384.00	14.15	195.40	143.00	1,170.40
25	ROADWAY SPAN					30,544.00	55.62	1,046,965.08	135.00	4,123,440.00
26	BR'DEE BALL LINES	1				23,063.00	65.15	271,463.19	100.79	3,708,224.10
27	ROADWAY FORMS, EAST AND WEST LENGTH (10'L)					5,423.00	47.75	259,043.75	-1.00	-5,423.00
28	EAST AND WEST LENGTH (10'L) CENTER LINE					4,788.00	89.00	426,132.32	37.25	176,353.00
29	WEST UNDER CANTILEVER END SPANNING 10' 0" (120'L)					1,932.00	83.00	179,670.00	37.25	71,967.00
30	SQUELTERS, EAST LEAF	12 120 (LBS.)				1,440.00	53.41	76,919.40	133.67	192,484.80
30	SQUELTERS, WEST LEAF	8 120 (LBS.)				980.00	49.95	47,904.00	133.67	128,370.20
31	PLATE, 1/2" THICK, PWT CHORD BETWEEN 10-10 AND 12-12	1				8,804.00	21.15	207,373.84	104.74	1,063,537.56*
32	ROADWAY CURB	2				37.50	92.25 FT.*	386,754.56	135.92*	966,071.75*
	TOTALS					(EAST LEAF) 791,678.32*		43,036,480.71*		88,423,698.25*
						(WEST LEAF) 795,562.37*		43,036,303.27*		88,402,918.77*
	TOTAL. WEIGHT					(EAST LEAF) 100,460.32				
						(WEST LEAF) 100,453.37*				
	UNBALANCED X MOMENT,					(EAST LEAF) 5,671,712.08*				
	IN FT-LBS.					(WEST LEAF) 5,673,554.59*				
	UNBALANCED Y MOMENT,					(EAST LEAF) 20,604,904.75*				
	IN IN-LBS.					(WEST LEAF) 20,584,125.27*				
COUNTERWEIGHT ADDED (EAST SIDE)	695*	450 PCF				312,750*	18.13*	5,670,157.50*	65.88*	20,603,970.00*
COUNTERWEIGHT ADDED (WEST SIDE)	695*	450 PCF				312,750*	18.14*	5,673,285.00*	65.81*	20,582,077.50*

Roosevelt Rd. Bascule


Truss Line Input

- Section Properties calculated in Excel, accounting for section loss as required*
 - Ag, An, Material, Ix, ly, Sx, Sy*
 - Section Loss (if applicable)*



MEMBER:		1-3				DESIGNATES USER INPUT							
No.	Section	X _t (in)	Y _t (in)	A _t (in ²)	I _x (in ⁴)	I _y (in ⁴)	d _x (in)	d _y (in)	A _X (in ²)	A _Y (in ²)	I _{x+A_d_x²} (in ⁴)	I _{y+A_d_y²} (in ⁴)	
1	L6x4x3/8	3.06	1.94	3.61	13.47	4.90	12.25	9.31	11.05	7.00	326.37	546.85	
2	L6x4x3/8	3.06	20.56	3.61	13.47	4.90	12.25	-9.31	11.05	74.22	326.37	546.85	
3	L6x4x3/8	27.57	1.94	3.61	13.47	4.90	-12.25	9.31	99.51	7.00	326.37	546.85	
4	L6x4x3/8	27.57	20.56	3.61	13.47	4.90	-12.25	-9.31	99.51	74.22	326.37	546.85	
5	22x7/16	4.22	11.25	9.63	388.21	0.15	11.09	0.00	40.61	108.28	388.21	1184.71	
6	22x7/16	26.41	11.25	9.63	388.21	0.15	-11.09	0.00	254.16	108.28	388.21	1184.71	
7							0.00	0.00	0.00	0.00	0.00	0.00	
8							0.00	0.00	0.00	0.00	0.00	0.00	
9							0.00	0.00	0.00	0.00	0.00	0.00	
10							0.00	0.00	0.00	0.00	0.00	0.00	
		$\Sigma = 33.69$				515.88 379.01 2081.90 4556.82							
GROSS PROPERTIES													
$\bar{x} = 15.31$ in		$r_x = 7.86$ in		$\bar{y} = 11.25$ in		$r_y = 11.63$ in		$A_t = 33.69$ in ²		$Weight = 0.11$ k/ft		$A_g = 2081.90$ in ²	
$I_x = 4556.82$ in ⁴		$S_{x,top} = 185.06$ in ³		$S_{x,bot} = 185.06$ in ³		$S_y = 297.59$ in ³		$I_y = 556.82$ in ⁴		$S_y = 297.59$ in ³		$Depth = 22.50$ in	
Net Properties													

Roosevelt Rd. Bascule Trussed Floorbeams

- *Moveable Span elements mostly rated in BrR*
- *Supplemental analysis independent of BrR for trussed floorbeams*
 - *Floorbeam 2-2*
 - *Floorbeam 10-10*




Floorbeam 2-2



Floorbeam 10-10

Roosevelt Rd. Bascule Carrying Elements

- *Fixed Span elements mostly rated in BrR*
- *Supplemental analysis required outside of BrR for some carrying elements*
 - *Cross Girder (Trunnion Floorbeam)*
 - *Stub Columns*




Cermak Rd. Bascule Scherzer Rolling Lift Bascule Bridge



2018 RADBUG MEETING - BOISE, IDAHO



Cermak Rd. Bascule Bridge Lift



2018 RADBUG MEETING - BOISE, IDAHO



Cermak Rd. Bascule Original Construction

Construction/Repair History

- **1906: Original Construction**
- **1995: Majority of structure replaced as part of rehabilitation**
 - Truss top and bottom chords, verticals and diagonals
 - Segmental and Track Girders
 - Anchor Girder and Columns
 - Bumping Girder
 - Floorbeams and Stringers
- **1996: Deck replacement and rebalancing**
- **1,064 existing plan sheets**

Geometry

- **216'-0" CL to CL 'First Positions of Roll'**
- **29'-4" & 25'-10 ½" End Spans (each side)**


• Design Load (Original)

L.L. For trusses: 3000# per lin ft of bridge occupying 22' in width of roadway and a load of 90# per sq ft for remainder of roadway and sidewalk.


For floor system and hangers: A concentrated load of 24 tons on two axles 10ft. ctrs. on any portion of the roadway, or on each car track for a space of 12' in width for each single track and 22' for double track and in addition a load of 100# per sq ft of remaining surface of roadway and sidewalk.

• Design Load (1994 CDOT specifications)


LIVE LOADS (LL)
ROADWAY - HS20-44 AND EQUIVALENT UNIFORM LANE LOADING = 1000LBS/LIN.FT.
- TRUCK LOADING AS SPECIFIED IN DESIGN STANDARDS FOR CHICAGO BASCULE BRIDGES AND SHOWN BELOW



Cermak Rd. Bascule Bascule Structure Components and Supports





Cermak Rd. Bascule Plan and Elevation



2018 RADBUG MEETING - BOISE, IDAHO




Cermak Rd. Bascule Cross Section



Cermak Rd. Bascule Load Stages


BRIDGE OPEN

Dead Load + Wind Load



BRIDGE CLOSED

Dead Load + Live Load (Including Pedestrian Load)



Cermak Rd. Bascule Dead Load Forces

Dead Loads


- Truss member self weight
- Floorbeams
- Stringers
- Cantilever sidewalks
- Lateral Bracing
- Deck (Steel Grating)
- Counterweight
- Mechanical Housing

MATERIAL - CARBON STEEL 1" ♦ RIVETS	TOTAL AREA PROVIDED		CROSS SECTION
	SG. INCHES	G.R. NET	
4L8 - 6x4x3/8" + 14.00 2W60x-22.5" + 19.25	33.60	1-3	[]
4L8 - 6x4x3/8" + 14.44 + 3.38 + 1.00 2W60x-22.5" + 19.25 + 9.94 + 1.51	33.60	2-5	do
4L8 - 6x4x3/8" + 27.76 - 6.75 + 2.01 2W60x-22.5" + 22.00 - 4.50 + 1.50	64.76	5-7	[]
4L8 - 6x4x3/8" + 10.82 - 7.67 + 0.60 2W60x-22.5" + 9.20 - 2.85 + 0.55	102.92	6-9	[]
4L8 - 6x4x3/8" + 36.92 - 7.87 + 0.95 2W60x-22.5" + 22.00 - 5.50 + 2.10	136.92	9-11	[]
4L8 - 6x4x3/8" + 36.92 - 7.87 + 0.95 2W60x-22.5" + 22.00 - 5.50 + 2.10	172.38	11-13	[]
4L8 - 6x4x3/8" + 36.92 - 7.87 + 0.95 2W60x-22.5" + 22.00 - 5.50 + 2.10	283.88	13-15	[]




Cermak Rd. Bascule Dead Load Balancing


- 1906: Original Balancing
- 1996: Rebalancing



Original Blocks




1996 Rebalancing



Cermak Rd. Bascule Carrying Elements

- *Fixed Span roadway elements mostly rated in BrR*
 - *Supplemental analysis required outside of BrR for some carrying elements*
 - *Anchor Girder and Column*
 - *Bumping Girder*



2018 RADBUG MEETING - BOISE, IDAHO



Using BrR To Evaluate Bascule Bridges

2018 RADBUG MEETING – BOISE, IDAHO

AUGUST 7-8, 2018



A Joint Venture Teaming of Alfred Benesch &
Company and Collins Engineers, Inc.

Thank You!
Questions?

