

BrR Construction Staging



BrR User Group
Alan Buehrig, ITD



BrR Construction Staging

- Where did this requirement come from?
- How do things work now and how will they need to change?
- ITD policy changes
- Recent example
- Reanalysis

National Bridge Inspection Standards (NBIS)

23 CFR 650 Subpart C

Revised May 6, 2022

§ 650.303 Applicability.

The National Bridge Inspection Standards (NBIS) in this subpart apply to all structures defined as highway bridges located on all public roads, on and off Federal-aid highways, including tribally-owned and federally-owned bridges, private bridges that are connected to a public road on both ends of the bridge, temporary bridges, and bridges under construction with portions open to traffic.

National Bridge Inspection Standards (NBIS)

(b) *Initial inspection.* Perform an initial inspection in accordance with [Section 4.2](#), AASHTO Manual (incorporated by reference, see [§ 650.317](#)) for each new, replaced, rehabilitated, and temporary bridge as soon as practical, but within 3 months of the bridge opening to traffic.

(2) Develop and document procedures for completion of new and updated bridge load ratings. Load ratings must be completed as soon as practical, **but no later than 3 months after the** initial inspection and when a change is identified that warrants a re-rating such as, but not limited to, changes in condition, reconstruction, new construction, or changes in dead or live loads.

BrR Construction Staging


- Where did this requirement come from?
- How do things work now and how will they need to change?
- ITD policy changes
- Recent example
- Reanalysis

National Bridge Inspection Standards (NBIS)

Much more than just “inspection” regulations.

4 Main Parts:

- Inspection
- Load Rating
- Permits
- Scour



ITD Staff

Alan Buehrig
Program Manager

**Inspection
Engineers/Load
Raters**
1 PE
3 EITs

Inspection Techs
2 Team Leaders
1 Trainee

UBIT
2 CDL Drivers

BrM Database
1 Project Manager
1 Specialist

**Sign Structure
Program**
1/3 Engineer

Hydraulic Program
1 1/3 Engineer

Permits
1/3 Engineer

**HELP
WANTED**

ITD Load Rating Processing

Load Rating Package

- BrR Model
- Larsa Model
- LRS (LFR)
- LRS (LRFR)
- Supplemental Calcs



ITD Load Rating



ITD Load Rating Processing

QA Review

-Melissa Henessy
-Alan Buehrig
-Kayla Jacobsen (Forsgren)
-Don Vander Boegh (VBE)

Internal Rating Tracking - Initial Analysis

Wednesday, February 3, 2021 8:43 AM

| BRKEY (Rating done) | District | Project KN | Drawing # | Material | Design | Due Date | RATER | CHECKER | SIR (QC) | DATE RATING COMPLETE | DATE CHECKING COMPLETE | DATE CORRECTIONS COMPLETE | DATE BACK CHECK COMPLETE | DATE SIR (QA) CHECK COMPLETE | DATE SIR (QA) CORRECTIONS COMPLETE | DATE SIR (QA) COMPLETED | READY TO PROCESS | SENT TO PATY | Comment |
|-----------------------------------|----------|---------------|-----------|-------------------------|-----------------|----------|---------------------------------|----------|----------|----------------------------|------------------------------|---------------------------------|--------------------------------|------------------------------------|--|----------------------------|---------------------|-----------------|--|
| 17696 Deck Bulb Tee | 4 | 19404 | 17576 | Prestressed Concrete | Stringer/Girder | 2/1/2021 | Tony Azari | Willi J. | Elsa | | 2/5/2021 | ##### | 2/16/2021 | 3/24/2021 | 3/30/2021 | 4/1/2021 | X | X | PK 19404, DRW 17576. Tony Azari designed, load rating is unknown status. |
| 28633 | 3 | | 17993 | Steel | Culvert | 2/1/2021 | Jake L. Done by AI Engineers | Scott L. | Melissa | 2/25/2021 | 3/24/2021 | 4/12/21 | 4/12/2021 | 4/19/2021 | 4/21/21 | 4/21/21 | 4/21/21 | | Sent to AI. 6' dia. Pipes. 10" fill causes low rating. 12' min. required. Assign to AI Engineers. |
| 10584 | 2 | 21964 | 17773 | Steel | Culvert | 2/7/2021 | Scott L. | Anthony | Melissa | 3/24/2021 | 4/7/2021 | 4/12/2021 | 4/12/2021 | 4/19/2021 | 5/4/2021 | 9/3/2021 | 9/14/2021 | 9/16/2021 | Done. PK 21964, DRW 17773, Designed by Great West/Rick Jensen, needs QA |
| 16876 Deck Bulb Tee | 1 | 19188 | 17644 | Prestressed Concrete | Stringer/Girder | 2/9/2021 | Leonard R./Sarah G. | Mike J. | Melissa | 1/24/2019 | 2/26/2019 | 3/4/2019 | - | 5/19/2021 | 5/19/2021 | 7/22/2021 | 7/22/2021 | 7/22/2021 | Done. Melissa updated rating for construction changes and other needed updates. Mike backchecked (he checked it originally). |

Bridge Key # _____
District# _____

ITD QA Load Rating Review
(Reanalysis)
(Circle One) State System or Local/Off System
Required Posting: Y or N

Load Rater
Name: _____
Date: _____
Company: _____
☐ Idaho PE

Checker
Name: _____
Date: _____
Company: _____
☐ Idaho PE

Quality Control (QC)
Structural Independent Review Sign
Name: _____
Date: _____
Company: _____
Must be an Idaho PE

Quality Assurance (QA)
☐ Combined Checker/QC/QA for Reanalysis Deck Change Only (Level 3 Required)
Name: _____
Date: _____
Company: _____
Must be Idaho PE & Must be Different Consultant than QC

Level of QA Review: (highlight one)
Level 1: Cursory Check (Start at Part 3)
Level 2: Spot Check (Start at Part 2)
Level 3: Complete Check (Start at Part 1)

| COMPONENT | RATING METHOD | | | | ATTACHMENTS (highlight those that apply) | | | |
|----------------|---------------|-----|-----|------|--|----------------------------|-------|-------|
| Deck | EJ | ASR | LFR | LRFR | BrR | Calcs (Mathcad/Excel) | Model | Rules |
| Superstructure | EJ | ASR | LFR | LRFR | BrR | Sup. Calcs (Mathcad/Excel) | Model | Rules |
| Substructure | EJ | ASR | LFR | LRFR | BrR | Sup. Calcs (Mathcad/Excel) | Model | Rules |

Part 1
Run the New Model and Compare to LRS
Doesn't Match
Investigate
Return to Rater for correction (attach screenshots of concerns)
Verified
Part 2
Reconcile QC - Verify all Checker and QC comments addressed by Rater and QC form completed.
Needs Reconciliation
Verified
Part 3
Evaluate for Additional Concerns
Recommended Follow-up: (as applicable circle)
LHTAC Review
Inspection QA
Rehab Project
Specialized Load Rating Refinement
Note to Inspector: _____
Process Complete

Bridge Factor/Route Color/Truck
☐ Reanalysis
Existing _____
New _____


BrR Version: _____

Inspection Report:
Deterioration: CS3 and CS4 defects needing LR deterioration have been taken into account.
Model Discrepancies: Cursory check for discrepancies from inspection report compared to model and compared to plans if necessary.

Needs Reconciliation
Verify Notes on LRS and adjust if needed

Processing
☐ Fill in Load Rating OneNote tracking dates.
☐ Update Follow-up Notes
☐ Switch out old Model in BrR to New Model Date _____
☐ Send Email to Jake for Color Route Capacity Map Change (if applicable)
☐ Cleanup load rating file for processing. Include final .pdf of Files
☐ Complete Load Rating File Update Coversheet
☐ Combine PDF LR Summary Sheet(s), QA Form, and LR File Coversheet
☐ Send Email to Lynette "Ready to Process" Include Hyperlink to LR Folder
☐ Include in Email Note to Inspector (if Needed)
☐ Update OneNote for any Recommended Follow-up
*At discretion of QA Engineer

QA Review

| | | | | |
|---|--|--|--|--|
| Bridge Key # _____ District# _____ | | ITD QA Load Rating Review (Reanalysis) (Circle One): State System or Local/Off System Required Posting: Y or N | |  4/9/25 |
| <u>Load Rater</u> Name: _____ Date: _____ Company: _____ <input type="checkbox"/> Idaho PE | <u>Checker</u> Name: _____ Date: _____ Company: _____ <input type="checkbox"/> Idaho PE | <u>Quality Control (QC)</u> <i>Structural Independent Review SIR</i> Name: _____ Date: _____ Company: _____ <i>Must be an Idaho PE</i> | <u>Quality Assurance (QA)</u> <input type="checkbox"/> Combined Checker/QC/QA for Renalayiss Deck Change Only (Level 3 Required) Name: _____ Date: _____ Company: _____ <i>Must be Idaho PE & Must be Different Consultant than QC</i> | |

Quality assurance (QA). The use of **sampling** and other measures to assure the **adequacy** of QC procedures in order to verify or measure the quality level of the **entire bridge inspection and load rating program.**

ITD Load Rating Processing

Update LR File



-BrR Database

-BrM Database

-Promiles Update

-Local Jurisdiction

BrR Database Update

Replace Existing File with New File – BrR 7.5.1

| | | | | | | |
|------------|------------------------------------|-----------------------|--|-----------------------------------|---|---|
| Bridge ID: | <input type="text" value="14526"/> | NBI structure ID (8): | <input type="text" value="000000000014526"/> | <input type="checkbox"/> Template | <input checked="" type="checkbox"/> Bridge completely defined | <input checked="" type="checkbox"/> Superstructures |
| | | | | | | <input type="checkbox"/> Culverts |
| | | | | | | <input type="checkbox"/> Substructures |

| Description | Description (cont'd) | Alternatives | Global reference point | Traffic | Custom agency fields | |
|------------------------|--|--------------|------------------------|---------|----------------------|--|
| Name: | <input type="text" value="05010A 4.68"/> | | | | Year built: | <input type="text" value="2023"/> |
| Description: | <div>Simple 2 Span CPS Girder Bridge over I-84 Bridge Key: 14526 Design Truck: HL-93</div> | | | | | |
| Location: | <input type="text" value="8.9 E. Twin Falls"/> | | | | Length: | <input type="text" value="212.00"/> ft |
| Facility carried (7): | <input type="text" value="SH 50"/> | | | | Route number: | <input type="text" value="00050"/> |
| Feat. intersected (6): | <input type="text" value="I 84 EB-WB;Kimberly IC"/> | | | | Mi. post: | <input type="text" value="4.70"/> |
| Default units: | <input type="text" value="US Customary"/> | | | | | |

BrM Database Update

Load Rating Coversheet


| ITD Load Rating Update Coversheet | | | | | | | | | |
|---|---|--|---|--|--|--|--|--|--|
| District# <u>3</u> | <u>State System</u> or Local/Off System (Highlight One): | | LR Processor: <u>Name: Kayla Jacobsen</u> | | | | | | |
| Owner: <u>ITD</u> | Rating Method B.LR.04): <u>LFR</u> (Rating Method for Operating Bridge May Differ) | | Company: <u>Forsgren</u> | | | | | | |
| Bridge Key # <u>15805</u> | Date: <u>06/30/2025</u> | | | | | | | | |
| Reason For Rating: | | | | | | | | | |
| New Rating: | | | | | | | | | |
| Modifications to Existing Rating: | | | | | | | | | |
| Inspection Generated: | | | | | | | | | |
| Administrative Generated: | | | | | | | | | |
| Original Stamped Rating: | | | | | | | | | |
| LR Based On: (Check those that apply) | | | | | | | | | |
| Field Sketches | | | | | | | | | |
| Design Plans | | | | | | | | | |
| Shop Drawings | | | | | | | | | |
| Engineer: <u>Elsa Zimmerly (HDR)</u> | | | | | | | | | |
| Date: <u>5/21/2010</u> | | | | | | | | | |
| Inspection | | | | | | | | | |
| Rating Method(s) | | | | | | | | | |
| Rating Application | | | | | | | | | |
| Component(s) Included | | | | | | | | | |
| How to Permit | | | | | | | | | |
| Load Rating Category: <u>LBSL</u> (4 Letters) | | | | | | | | | |
| LR Event Summary (Include ALL Updated Events for LR File) | | | | | | | | | |
| REPORT AS FHWA REQUEST | | | | | | | | | |
| Load Rating Summary | | | | | | | | | |
| ITD Controlling Rating Event For Operating Bridge: (Date, Component, Rating Method) | | | | | | | | | |
| Controlling Truck: <u>Idaho-Type 3</u> | | | | | | | | | |
| Controlling Member: <u>Exterior Girder</u> | | | | | | | | | |
| Required Posting: Y or <u>N</u> | | | | | | | | | |

| Culvert | Bridge | Date | RATING METHOD (highlight one per line) | | | | ATTACHMENTS (highlight those that apply) | | | | REPORT AS FHWA REQUEST | |
|--------------------------|----------------|------------|---|-----|-----|------|--|---------|-------|-------|------------------------|-------------------------------------|
| <input type="checkbox"/> | Deck | | EJ | ASR | LFR | LRFR | BrR | Mathcad | Excel | Model | Rules | <input type="checkbox"/> |
| | | | EJ | ASR | LFR | LRFR | BrR | Mathcad | Excel | Model | Rules | <input type="checkbox"/> |
| | | | EJ | ASR | LFR | LRFR | BrR | Mathcad | Excel | Model | Rules | <input type="checkbox"/> |
| <input type="checkbox"/> | Superstructure | 08/26/2024 | EJ | ASR | LFR | LRFR | BrR | Mathcad | Excel | Model | Rules | <input checked="" type="checkbox"/> |
| | | | EJ | ASR | LFR | LRFR | BrR | Mathcad | Excel | Model | Rules | <input type="checkbox"/> |
| | | | EJ | ASR | LFR | LRFR | BrR | Mathcad | Excel | Model | Rules | <input type="checkbox"/> |
| <input type="checkbox"/> | Substructure | | EJ | ASR | LFR | LRFR | BrR | Mathcad | Excel | Model | Rules | <input type="checkbox"/> |
| | | | EJ | ASR | LFR | LRFR | BrR | Mathcad | Excel | Model | Rules | <input type="checkbox"/> |
| | | | EJ | ASR | LFR | LRFR | BrR | Mathcad | Excel | Model | Rules | <input type="checkbox"/> |

| FHWA Reporting: | | Load Rating Summary | | ITD Controlling Rating Event For Operating Bridge: | |
|-------------------------------------|-------------|--|--|--|--|
| Inventory Factor (B.LR.05): | <u>0.84</u> | | | (Date, Component, Rating Method) | |
| Operating Factor (B.LR.06): | <u>1.39</u> | | | <u>08/26/2024 Superstructure LFR</u> | |
| Controlling Legal Factor (B.LR.07): | <u>1.51</u> | Controlling Truck: <u>Idaho-Type 3</u> | | Bridge Factor: <u>824</u> | |
| Routine Permit Load (B.LR.08): | <u>A</u> | Controlling Member: <u>Exterior Girder</u> | | Route Color: <u>Purple</u> | |

BrM Database Update

ITD Load Rating Update Coversheet



4/17/25
Page 1 of 1

District# 3

Owner: ITD

Bridge Key # 15805

State System or Local/Off System
(Highlight One):

Rating Method B.LR.04): LFR
(Rating Method for Operating Bridge May Differ)

LR Processor:

Name: Kayla Jacobsen

Company: Forsgren

Date: 06/30/2025

Reason For Rating:

New Rating:

- ☐ New Bridge to Inventory
- ☐ Staged construction
- ☐ Complete Rebuild of LR

Modifications to Existing Rating:

Inspection Generated

- ☒ **Wearing Surface Change**
- ☐ Rehabilitation/Repair
- ☐ Reanalysis due to Deterioration
- ☐ LR recertification From NBI Inspection

Administrative Generated:

- ☐ Rating Code Update
- ☐ Rating Program Update
- ☐ Additional Vehicles
- ☐ Quality Assurance Check

Original Stamped Rating

Engineer:

Elsa Zimmerly (HDR)

Date:

5/21/2010

LR Based On:

(Check those that apply)

- ☐ Field Sketches
- ☒ **Design Plans**
- ☒ **Shop Drawings**

BrM Database Update

| <u>RATING METHOD(S)</u> | <u>RATING APPLICATION</u> | <u>COMPONENT(S) INCLUDED</u> | <u>HOW TO PERMIT</u> |
|-------------------------|--|-------------------------------------|--|
| N - None | N - None | N - None | N - None |
| E - EJ | O - BARS | C - Culvert Model* | L - BrR Model(AASHTO) LFR |
| S - ASR | J - EJ | D - Deck Only | R - BrR Model (AASHTO) LRFR |
| L - LFR | B - BrR Model (AASHTO) only | S - Superstructure Only | S - Software Only |
| R - LRFR | C - BrR Model (AASHTO) and Calcs (Mathcad or Excel) | F - Substructure Only | X - Rules Only |
| C - ASR & LFR | M - BrR Model (AASHTO), Calcs (Mathcad or Excel) and LARSA Model | B - Deck and Superstructure | F - Factor |
| B - ASR/LFR & LRFR | T- No BrR Model, Calculations and LARSA Model | L - Substructure and Superstructure | C - Combination of BrR and Calcs and/or Model and/or Rules |
| A - EJ & LFR/ASR | Z - Other | A - Deck, Super and Substructure | |
| T- EJ, LFR/ASR, LRFR | | | |

Load Rating Category:
LBSL

 (4 Letters)

(Highlight One Item per Column) *Refers to LR Approach Only.

BrM Database Update

| <u>LR Event Summary</u> (Include ALL Updated Events for LR File) | | | | | | | | | | | | <u>REPORT</u> <u>AS FHWA</u> <u>LR EVENT</u> |
|--|--|-------------|--|-----|-----|------|---|---------|-------|-------|-------|--|
| <u>Culvert</u> | <u>Bridge</u> | <u>Date</u> | <u>RATING METHOD</u> (highlight one per line) | | | | <u>ATTACHMENTS</u> (highlight those that apply) | | | | | |
| <input type="checkbox"/> Culvert | <input type="checkbox"/> Deck | | EJ | ASR | LFR | LRFR | BrR | Mathcad | Excel | Model | Rules | <input type="checkbox"/> |
| | | | EJ | ASR | LFR | LRFR | BrR | Mathcad | Excel | Model | Rules | <input type="checkbox"/> |
| | | | EJ | ASR | LFR | LRFR | BrR | Mathcad | Excel | Model | Rules | <input type="checkbox"/> |
| | <input checked="" type="checkbox"/> Superstructure | 08/26/2024 | EJ | ASR | LFR | LRFR | BrR | Mathcad | Excel | Model | Rules | <input checked="" type="checkbox"/> |
| | | | EJ | ASR | LFR | LRFR | BrR | Mathcad | Excel | Model | Rules | <input type="checkbox"/> |
| | <input checked="" type="checkbox"/> Substructure | | EJ | ASR | LFR | LRFR | BrR | Mathcad | Excel | Model | Rules | <input type="checkbox"/> |
| | | | EJ | ASR | LFR | LRFR | BrR | Mathcad | Excel | Model | Rules | <input type="checkbox"/> |
| | <input type="checkbox"/> Substructure | | EJ | ASR | LFR | LRFR | BrR | Mathcad | Excel | Model | Rules | <input type="checkbox"/> |

BrM Database Update

| FHWA Reporting: | | <u>Load Rating Summary</u> | | ITD Controlling Rating Event For Operating Bridge: | |
|-------------------------------------|-------------|--------------------------------------|------------------------|--|---------------|
| Inventory Factor (B.LR.05): | <u>0.84</u> | <i>(Date_Component_RatingMethod)</i> | | | |
| Operating Factor (B.LR.06): | <u>1.39</u> | <u>08/26/2024 Superstructure LFR</u> | | | |
| Controlling Legal Factor (B.LR.07): | <u>1.51</u> | Controlling Truck: | <u>Idaho-Type 3</u> | Bridge Factor: | <u>824</u> |
| Routine Permit Load (B.LR.08): | <u>A</u> | Controlling Member: | <u>Exterior Girder</u> | Route Color: | <u>Purple</u> |
| Required Posting: Y or N | | | | | |

Promiles Update

- Occurs Quarterly
- Involves Extensive Testing and Coordination
- 511 Updates Can Occur as Permitting Restriction When Necessary

BrR Construction Staging

- Where did this requirement come from?
- How do things work now and how will they need to change?
- **ITD Policy Changes**
- Recent Example
- Reanalysis

Addressing New Policy

- Policy Solution
 - New Bridge Rule
 - Rules about Staged Construction Bridges
- Specific Staging Ratings for Bridges
 - New Bridge
 - Old Bridge



Policy Solution

6.0.3—Staged Construction

In addition to the load rating procedures in the BDM, the BrR model shall include a staged construction superstructure definition for each portion of the bridge that will be used for traffic staging. Staged construction shall abide by the following requirements:

- 1.) The staged construction superstructure definitions shall be included with the final design submittal of the load rating and revised as needed for the PS&E submittal.
- 2.) A load rating summary (LRFR and LFR) shall be submitted for the staged construction in addition to the full structure. The HL-93 LRFR inventory rating for each staged construction superstructure definition shall be 1.00 or higher.
- 3.) Any staged construction of the existing bridge or new bridge shall have an HS-20 rating factor at least as high as the existing bridge (unless approved by the Group Leader).
- 4.) As stated in the BDM, the HL-93 LRFR inventory rating, including future loads, shall be 1.10 or higher for new bridges on the state system, unless approved by the Group Leader.

Policy Solution

New Bridge Rule


Limited to:

- 70 kip max axle group
- 35 kip max axle

BrR Construction Staging

- Where did this requirement come from?
- How do things work now and how will they need to change?
- ITD Policy Changes
- **Recent Example**
- Reanalysis


Example – Kimberly IC I-84





Example – Kimberly IC I-84




Example – Kimberly IC I-84



Example – Kimberly IC I-84



Example – Kimberly IC I-84



Example – Kimberly IC I-84




1. Approach plus milepost.

Example – Kimberly IC I-84



2. Right side.

Example – Kimberly IC I-84














Example – Kimberly IC I-84



1. Approach plus milepost.

Example – Kimberly IC I-84

| Name | Date modified | Type | Size |
|---|--------------------|----------------------|----------|
|  14526_0124_InspReport | 1/24/2024 1:35 PM | PDF Document | 1,174 KB |
|  14526_0524_LRS_LRFRandLFR | 5/8/2024 11:59 AM | PDF Document | 244 KB |
|  14526_LFR_LRS_STAGE 1 Construction | 5/8/2024 8:47 AM | PDF Document | 122 KB |
|  14526_LFR_LRS_STAGE 1 Construction | 5/8/2024 8:48 AM | Microsoft Excel W... | 3,217 KB |
|  14526_LRFR_LRS_STAGE 1 Construction | 5/8/2024 8:46 AM | PDF Document | 138 KB |
|  14526_LRFR_LRS_STAGE 1 Construction | 5/8/2024 8:47 AM | Microsoft Excel W... | 3,277 KB |
|  20675 Bridge Plans | 1/25/2024 9:47 AM | PDF Document | 5,593 KB |
|  20675 LRFR LRS | 2/4/2022 3:34 PM | Microsoft Excel M... | 3,200 KB |
|  20675_LRS | 2/4/2022 3:34 PM | PDF Document | 234 KB |
|  20675LRFR | 2/4/2022 3:34 PM | XML Document | 684 KB |
|  QA Comment Form_HDR_ITD (005) | 2/22/2022 12:53 PM | Microsoft Excel W... | 26 KB |

Example – Kimberly IC I-84

- LRS LFR For staged construction
- Staged Construction Watermark



ASR/LFR BRIDGE LOAD RATING SUMMARY

rev. 3/1/2021

Page 1

| | | | | | |
|--|------------------------------------|--|---|---|---|
| Bridge Key No. 14526 | Structure Name 05010A 4.68 | (27) Year Built 2023 | (106) Year Reconstruct N/A | Inspection Date 1/22/2024 | Inventory Data Date 4/9/2024 |
| (9) Bridge Location 8.9 E. TWIN FALLS | (7) Facility Carried SH 50 | (6a) Feature Intersected I 84 EB-WB;KIMBERLY IC | Drawing Number 18057 | | |
| (49) Length 212 ft. | (11) Milepost 4.700 | (2) District 4 | (3) County Jerome | (22) Owner State Highway Agency | Administrative Jurisdiction District 4 |
| (45, 43a, 43b) Bridge Description 2 Span Prestressed Concrete Stringer/Girder | | (31) Design Load (per plans) HL-93 | Granular WS N/A in. | Asphalt WS N/A in. | Concrete WS N/A in. |
| Rating Program & Version BrR 7.2 - AASHTO Engine | | Rating Method LFR | AASHTO Reference The Manual for Bridge Evaluation, Third Edition, 2018 | | |
| (58) Deck 9 Excellent | (59) Superstructure 9 Excellent | (60) Substructure 9 Excellent | (62) Culvert N N/A (NBI) | (113) Scour Critical N Not Over Waterway | |
| (30) ADT Year 2022 | (29) ADT 7100 | (109) Truck % ADT 14 | ADTT (ADT x Truck % ADT) 994 | (19) Detour Length 8 | Year Programmed N/A |

INVENTORY RATINGS

| Rating Vehicle | Controlling Configuration | Weight (Tons) | Controlling Member | Controlling Location | Controlling Limit State | Rating Factor | Rating (Tons) |
|------------------|---------------------------|---------------|--------------------|----------------------|------------------------------|---------------|---------------|
| HS-25 | Truck | 45 | G3 - Int. Gir. | 1.50 | PS Tensile Stress - Concrete | 0.85 | 38 |
| HS-20 | Truck | 36 | G3 - Int. Gir. | 1.50 | PS Tensile Stress - Concrete | 1.07 | 38 |
| Idaho - Type 3 | Truck | 27 | G3 - Int. Gir. | 1.50 | PS Tensile Stress - Concrete | 1.32 | 35 |
| Idaho - Type 3S2 | Truck | 39.5 | G3 - Int. Gir. | 1.50 | PS Tensile Stress - Concrete | 1.13 | 44 |
| Idaho - Type 3-3 | Truck | 39.5 | G3 - Int. Gir. | 1.50 | PS Tensile Stress - Concrete | 1.10 | 43 |
| Idaho - 121k | Truck | 60.5 | G3 - Int. Gir. | 1.50 | PS Tensile Stress - Concrete | 0.89 | 53 |
| NRL | Truck | 40 | G3 - Int. Gir. | 1.50 | PS Tensile Stress - Concrete | 0.93 | 37 |


OPERATING RATINGS

| Rating Vehicle | Controlling Configuration | Weight (Tons) | Controlling Member | Controlling Location | Controlling Limit State | Rating Factor | Rating (Tons) |
|------------------|---------------------------|---------------|--------------------|----------------------|-------------------------|---------------|---------------|
| HS-25 | Truck | 45 | G3 - Int. Gir. | 1.98 | Design Shear - Concrete | 1.85 | 83 |
| HS-20 | Truck | 36 | G3 - Int. Gir. | 1.98 | Design Shear - Concrete | 2.31 | 83 |
| Idaho - Type 3 | Truck | 27 | G3 - Int. Gir. | 1.40 | Design Shear - Concrete | 2.69 | 72 |
| Idaho - Type 3S2 | Truck | 39.5 | G3 - Int. Gir. | 1.98 | Design Shear - Concrete | 2.36 | 93 |
| Idaho - Type 3-3 | Truck | 39.5 | G3 - Int. Gir. | 1.98 | Design Shear - Concrete | 2.36 | 93 |
| Idaho - 121k | Truck | 60.5 | G3 - Int. Gir. | 1.98 | Design Shear - Concrete | 1.94 | 117 |
| NRL | Truck | 40 | G3 - Int. Gir. | 1.98 | Design Shear - Concrete | 2.19 | 87 |

BRIDGE LOAD RATING SUMMARY

| | | | | |
|---------------------------------------|-----------------------|----------------------------|------------------------------|--|
| Controlling Truck Idaho - Type 3-3 | Bridge Factor 1165 | Bridge Color Interstate | Load Posting Required? No | Max Axle Weight if Posting Req. N/A |
|---------------------------------------|-----------------------|----------------------------|------------------------------|--|

Example – Kimberly IC I-84



- Add a Separate Stage Construction Models as Necessary
- Staged Construction Model Will be Deleted after Completion of Bridge

Updating to Permitting

| A | B | C | D | E | F | G | H | I | J | K | L | M | N |
|--|---|---|--------|---|--------|---|---|---|---|---|---|---|---|
| ROUTE | | | BEG MP | | END MP | | | | | | | | |
| PASTE ROUTE HERE | | | | | | | | | | | | | |
| <div> <div> PERMIT VEHICLE INFORMATION <div> VEHICLE FACTOR (VF) WEIGHT (KIPS) NON-STANDARD GAGE </div> <div> No </div> </div> <div> ADD MISSING BRIDGE <div> ENTER BRIDGE KEY >> </div> <div> Add to BridgesCrossed tab </div> </div> <div> TOOLKIT INSTRUCTIONS <div> FIRST TIME USERS >> <ol style="list-style-type: none"> 1. Copy the route in the word d 2. Enter the Vehicle Factor and 3. Click 'Process Route' to gene 4. Click 'Verify BridgesCrossed' 5. Once bridges have been veri 6. Review bridges with commer </div> <div> ADDITIONAL NOTES <p>Use Load Rating Tool when possi</p> <p>LFD BRIDGES: Place Permit Vehi</p> <p>LRFR BRIDGES: Place Permit Vehi</p> </div> <div> LATEST REVISION NOTES <p>New BAM File: \\itdops\opsfiles\DEPP\</p> </div> </div> </div> | | | | | | | | | | | | | |
| <div> <div> FIND BRIDGES ALONG ROUTE <div> Process Route </div> </div> <div> VERIFY BRIDGES FOUND <div> Verify BridgesCrossed </div> </div> <div> POPULATE ANALYSIS TAB <div> Find Bridges to Analyze </div> </div> </div> <p>RECOMMENDED: Use Verify BridgesCrossed prior to populating analysis tab</p> <div> <div> ADD FORMS TO PERMIT FOLDER <div> Add a Form </div> </div> <div> QC AUTOMATED PERMITTING RESULTS <div> QC Bridge Study </div> </div> </div> <p>NOTE: Place Automated Permitting Bridge Study in same folder as toolkit file.</p> | | | | | | | | | | | | | |

BAM Factor *(NOTE: Toolkit searches for a sheet with the word "Factor" in its name.)*

Change BAM File Link

<\\itdops\opsfiles\DEPP\Bridge\AssetManagement\Permits\Factor Lists\2025\1-1-25\1-1-25 BAM Factor.xlsx>

| AF | AG | AH | AI | AJ |
|------|---------|--------|---------------|-----------------|
| | Routing | Rating | Additional | ITD Comment |
| #N/A | Rule | Rule | Over 35k Sing | New Bridge Rule |
| #N/A | Rule | Rule | Over 35k Sing | New Bridge Rule |
| #N/A | Rule | Rule | Over 35k Sing | New Bridge Rule |
| #N/A | Rule | Rule | Over 35k Sing | New Bridge Rule |
| #N/A | Rule | Rule | Over 35k Sing | New Bridge Rule |

BrR Construction Staging

- Where did this requirement come from?
- How do things work now and how will they need to change?
- ITD Policy Changes
- Recent Example
- **Reanalysis**

National Bridge Inspection Standards (NBIS)



(b) *Initial inspection.* Perform an initial inspection in accordance with [Section 4.2](#), AASHTO Manual (incorporated by reference, see [§ 650.317](#)) for each new, replaced, rehabilitated, and temporary bridge as soon as practical, but within 3 months of the bridge opening to traffic.

(2) Develop and document procedures for completion of new and updated bridge load ratings. Load ratings must be completed as soon as practical, **but no later than 3 months after the initial inspection** and when a change is identified that warrants a re-rating such as, but not limited to, changes in condition, **reconstruction, new construction, or changes in dead or live loads.**

LR Renalysis

Ratings Need to be backed by a Professional Engineer.

Load Rating Data is Presented as Part of the Inspection Report.



6.1.8—Qualifications and Responsibilities

A registered Professional Engineer shall be charged with the overall responsibility for bridge-capacity evaluation. The engineering expertise necessary to properly evaluate a bridge varies widely with the complexity of the bridge. A multi-disciplinary approach that utilizes the specialized knowledge and skills of other engineers may be needed in special situations for inspection and office evaluation.

6.1.9—Documentation of Load Rating

The load rating should be adequately documented, including all background information such as field inspection reports, material and load test data, all supporting computations, and a clear statement of all assumptions used in calculating the load rating. If a computer model was used, the input data file should be retained for future use.

LR Reanalysis

Historically 2 parallel tasks completed by separate groups:

- **Load Rating**
- **Inspection**

Effectiveness Concerns:

- 3 months is short!
- Limited Resources.
- Ratings are complex if left out of date.



ITD Load Rating Recertification

Limited Trial Basis FY25

- Tying back together 2 dependent parallel tasks (Inspection and LR).
- Most of Inspectors are now Engineers with LR capability and vice versa.
- 2 Consultants FY25

ITD Load Rating Recertification

ITD Load Rating Recertification

(Routine NBIS Inspection Generated)

Bridge Key # _____

District# _____

Owner: _____

LR QA Engineer: *Completed by ITD*

Name: _____

Company: _____

Date: _____

NBIS Inspection Date: _____

NBIS Team Lead: _____

**Load Rater or Checker Must
be Present During Inspection*

Load Rater**

☐ *Present During NBIS inspection**

Name: _____

Date: _____

Company: _____

***Load Rater or Checker Must be an Idaho PE*

Checker**

☐ *Present During NBIS inspection**

Name: _____

Date: _____

Company: _____

Quality Control (QC)

(Structural Independent Review)

Name: _____

Date: _____

Company: _____

Must be an Idaho PE

LR Renalysis

Complete and attach
Structural Review of all
CS4 Elements.
LR able to Resolve
Concern with Review?

LR Update Limited to Change to:

- Deck Wearing Surface
- BrR Version Upgrade
- Measurable Section Loss

(highlight those that apply)

Rating Application is an "J" or a "B"

Pre-SNBI Inspection Report

WEARING SURFACE and DEAD LOAD INFORMATION

| | | | |
|-----------|------------|-----------|------------|
| Asphalt: | 0.0 inches | Concrete: | 0.8 inches |
| Granular: | 0.0 inches | Timber: | 0.0 inches |

POSTING INFORMATION

WEIGHT

Load Analysis Date:

Bridge Factor:

Load Analysis Required: B Initial Analysis Req

Route Color:

Load Rating Analysis

Recommended

Actual

IR (tons)

OR (tons)

Posting(tons)

Posting(tons)

H Truck

HS Truck

Type3

Type 3S2

Type 3-3

Type3

Type 3S2

Type 3-3

Axle Limit

HEIGHT

Recommended

Actual

Height Posting:

ACTUAL WIDTH POSTING

Single Lane All Vehicles: N

Single Lane Trucks/Buses: N

SNBI Inspection Report

| Load Rating & Posting | | | | 10906 08/04/2029 |
|---------------------------------|--|-----------------------------|-------------------------|----------------------|
| Load Rating Event Data | | | | |
| Reason for Load Rating: | | Load Rating Date (B.LR.03): | 12/27/2023 | |
| Load Rater: | Will Johnson | Software Used: | AASHTOWare BRF | |
| Checker: | Scott Uitchfield | Secondary Software: | | |
| Quality Control Engineer: | | | | |
| Design Load (B.LR.01): | HL-93 | Asphalt Thickness: | | |
| Design Method (B.LR.02): | LRFD Load and Resistance Factor Design | Concrete Thickness: | 0.80 inches | |
| Rating Based On: | | Granular Thickness: | | |
| Load Rating Category: | | Timber Thickness: | | |
| Load Rating Method (B.LR.04): | LRFR Load and Resistance Factor Rating | Max WS for Load Capacity: | 0.00 inches | |
| Analysis Status: | Analysis Complete | | | |
| 12/27/2023 | | | | |
| 0 Design | | | | |
| Vehicle Name | Rating | Tons | Controlling Limit State | Controlling Location |
| HS-20 Operating | 2.17 | 78.12 | 1 Strength I - Flexure | G2 Int @ 1.50 |
| HS-20 Inventory | 1.31 | 47.16 | 1 Strength I - Flexure | G2 Int @ 1.50 |
| HL-93 Operating | 1.52 | 54.72 | 1 Strength I - Flexure | G1 Ext @ 1.50 |
| HL-93 Inventory | 1.17 | 42.12 | 1 Strength I - Flexure | G1 Ext @ 1.50 |
| 1 Legal | | | | |
| Vehicle Name | Rating | Tons | Controlling Limit State | Controlling Location |
| Idaho - 121k Operating | 1.70 | 102.85 | 1 Strength I - Flexure | G2 Int @ 1.50 |
| AASHTO Notational Rating Load | 1.93 | 77.20 | 1 Strength I - Flexure | G2 Int @ 1.50 |
| Idaho - 121k Inventory | 1.02 | 61.71 | 1 Strength I - Flexure | G2 Int @ 1.50 |
| NRL Inventory | 1.15 | 46.00 | 1 Strength I - Flexure | G2 Int @ 1.50 |
| HL-93 Idaho - Type 3 | 2.55 | 0.00 | 3 Strength II - Flexure | G2 Int @ 1.50 |
| HL-93 Idaho - Type 3S2 | 2.11 | 0.00 | 3 Strength II - Flexure | G2 Int @ 1.50 |
| HL-93 Idaho - Type 3-3 | 2.06 | 0.00 | 3 Strength II - Flexure | G2 Int @ 1.50 |
| HL-93 Idaho - 121k | 1.60 | 0.00 | 3 Strength II - Flexure | G2 Int @ 1.50 |
| HL-93 NRL | 1.79 | 0.00 | 3 Strength II - Flexure | G2 Int @ 1.50 |
| FHWA Type EV2 emergency vehicle | 2.47 | 71.01 | 3 Strength II - Flexure | G2 Int @ 1.50 |
| FHWA Type EV2 emergency vehicle | 2.64 | 75.90 | 1 Strength I - Flexure | G2 Int @ 1.50 |
| FHWA Type EV3 emergency vehicle | 1.63 | 70.09 | 3 Strength II - Flexure | G2 Int @ 1.50 |
| FHWA Type EV3 emergency vehicle | 1.74 | 74.82 | 1 Strength I - Flexure | G2 Int @ 1.50 |
| 2 Permit | | | | |
| Vehicle Name | Rating | Tons | Controlling Limit State | Controlling Location |
| Idaho - Type 3 Operating | 2.70 | 72.90 | 1 Strength I - Flexure | G2 Int @ 1.50 |
| Idaho - Type 3S2 Operating | 2.25 | 88.88 | 1 Strength I - Flexure | G2 Int @ 1.50 |
| Idaho - Type 3-3 Operating | 2.20 | 86.90 | 1 Strength I - Flexure | G2 Int @ 1.50 |
| Idaho - Type 3 Inventory | 1.63 | 44.01 | 1 Strength I - Flexure | G2 Int @ 1.50 |
| Idaho - Type 3S2 Inventory | 1.84 | 52.98 | 1 Strength I - Flexure | G2 Int @ 1.50 |
| Idaho - Type 3-3 Inventory | 1.82 | 52.14 | 1 Strength I - Flexure | G2 Int @ 1.50 |
| HL-93 Idaho - Type 3 | 4.04 | 0.00 | 3 Strength II - Flexure | G1 Ext @ 1.50 |
| HL-93 Idaho - Type 3S2 | 3.35 | 0.00 | 3 Strength II - Flexure | G1 Ext @ 1.50 |
| HL-93 Idaho - Type 3-3 | 3.27 | 0.00 | 3 Strength II - Flexure | G1 Ext @ 1.50 |
| HL-93 Idaho - 121k | 2.53 | 0.00 | 3 Strength II - Flexure | G1 Ext @ 1.50 |
| HL-93 NRL | 2.84 | 0.00 | 3 Strength II - Flexure | G1 Ext @ 1.50 |
| Notes / Remarks: | | | | |

| 10906 08/04/2029 | | | | | | | |
|---------------------------------|---|----------------|---|----------------------------|------------------------------|--------------------------------|----------------------------|
| Inspection Type | Required for Bridge Inspection Being Performed (B.I.E.01) | Inspector | Most Recent Inspection Date | Interval Method (B.I.E.07) | Interval (months) (B.I.E.08) | Inspection Due Date (B.I.E.06) | Inspection Assignment Name |
| In-Depth | Yes | Yes | Jack Irwin | 8/4/2025 | 48 | 8/4/2029 | |
| Routine | Yes | Yes | Jack Irwin | 8/4/2025 | 1 Method 1 | 24 | 8/4/2027 |
| Review Information | | | | | | | |
| Step | REVIEWER | Completed Date | Completed # of Days Since Inspection Begin Date | | | | |
| B478DD05F0644EC883467A8E16EDDC9 | | | | | | | |
| Days Remaining for Review | | | | | | | |

Questions
